




June 17, 2021

# 2021 Planning Advisory Group Meeting

# Northern Maine Transmission System



# Transmission Planning Collaboration

- Adjusted based on customer feedback
- Intent: spread out remaining required MPD rebuild plan over 15-20 years (total rebuild program will span nearly 30 years)
- Final plan subject to enhanced inspection findings (drone, resistograph, climbing)
- Line and targeted line segment rebuilds will be necessary

# Chapter 330 Plans & Adjustments

Summary of Past and Present Chapter 330 Reports												
Year	2018 Report			2019 Report			2020 Report			2021 Report		
	Project	Miles	Cost Range (\$M)	Project	Miles	Cost Range (\$M)	Project	Miles	Cost Range (\$M)	Project	Miles	Cost Range (\$M)
2018	6913 Mapleton	0.8	0.6 - 0.9									
	6913 PISS to Pole 160	1.8	1.0 - 1.5									
2019	6901 FF Tap	1.2	0.5 - 0.7	6901 FF Tap	1.2	0.5 - 0.7						
	6903 OC to Limestone	9.8	4.9 - 6.9	6903 Pole 57 - 126	3.8	2.8 - 3.8						
	6930 Maysville to Washburn	8.4	4.5 - 6.0	6913 PISS to Pole 160	1.8	1.0 - 1.5						
				1176 Str 98 to Border	0.8	0.65 - 0.85						
2020	6930 Washburn to Ashland	16.9	12.0 - 14.0	6930 Dow to Maysville	3.0	2.0 - 2.4	6903 Pole 57 - 126	3.8	2.85 - 3.8			
	6930 Dow to Maysville	3.0	1.5 - 2.0	1176 Str 41 to 97	6.4	4.1 - 5.1	1176 Str 42 - Border	7.2	5.5 - 6.0			
	6950 Westfield to MHSS	3.4	3.0 - 3.5									
2021	1176 Flos to Border	11.9	6.0 - 8.5	1176 Str 3 to 41	4.8	3.1 - 3.8	6930 Dow to Maysville	3.0	2.0 - 2.4	6930 Dow to Maysville	3.0	1.4 - 1.6
							1176 Str 3 to 41	4.8	3.1 - 3.8	1176 Str 42 - Border	7.2	6.0 - 6.5
									1176 Str 3 to 41	4.8	3.3 - 3.8	
2022	6915 Flos to NPI	3.0	1.5 - 2.0	6915 Flos to NPI	3.0	1.5 - 2.0	69053 Van Buren Tap	1.2	0.8 - 1.2	69053 Van Buren Tap	1.2	0.8 - 1.2
							69201 Mars Hill Tap	1.6	2.0 - 2.6	69201 Mars Hill Tap	1.6	2.2 - 2.6
2023				69032 Loring Tap	1.6	0.88 - 1.1	69032 Loring Tap	1.6	0.88 - 1.1	69032 Loring Tap	1.6	0.88 - 1.1
				6905 Phase 1	4.0	2.2 - 2.6	6905 Phase 1	4.0	2.2 - 2.6	6915 Flos to NPI	3.0	1.5 - 2.0
2024							6915 Flos to NPI	3.0	1.5 - 2.0	6950 Westfield to MHSS	3.4	3.0 - 3.5
							6950 Westfield to MHSS	3.4	3.0 - 3.5			
2025									6905 Phase 1	4.0	2.2 - 2.6	
Total Avg/Yr		60.2	35.5 - 40.0		30.4	18.7 - 23.0		33.6	23.8 - 29.0		29.8	21.3 - 24.9
		12.0	7.1 - 8.0		6.1	3.7 - 4.6		6.7	4.8 - 5.8		6.0	4.3 - 5.0

Designates Project Under Construction at time annual Chapter 330 Report filed (April 1)

# 2020 Project Work Completed

- Line 6903 - Limestone & Caribou (Rebuild Structure 57 to 127)
- Line 6905 – Grand Isle, Van Buren, Hamlin (Transmission Rebuild per Inspection)
- Line 6909 - Fort Kent, Frenchville, Madawaska (Transmission Rebuild per Inspection)
- Line 1176 - Easton (Rebuild Structure 42 to Border - Engineering & Permitting & Construction Starts)


# Line 6903 Rebuild (Caribou & Limestone)



**Brown glass post type insulators, cracked crossarms and rejected pole due to internal decay**



# Line 6903 Rebuild continued...




# Line 6903 Post Section Rebuild





# Line 1176 Rebuild Phase 1&2 - Previous



# Line 1176 Rebuild Phase 1&2 – New Line




Lack of H-frame  
"K" bracing leads  
to structure  
instability

# Line 1176 Rebuild Phase 1&2 – New Line



# Line 1176 Lightning Protection - Previous



# Line 1176 Rebuild Phase 1&2 - Previous



Lack of H-frame  
“X” bracing leads  
to structure  
instability

# Line 1176 Rebuild Phase 1&2 – New Line



Bank of H-frame  
bracing leads  
structure  
stability

# Line 1176 – Matting





# Emerging Issues

## System Condition

- **Line 6905**
- **Line 6909**




# Line 6905 Emergency Pole Replacements




**Excessive pole and crossarm rot detected by UAS (a.k.a. drone) inspection resulted in an emergency structure replacement project**

# Line 6905 Condition continued...



# Line 6905 Condition Continued...




# Line 6909 Condition

GIS Line no.	Str/Pole Number	City	Latitude	Longitude	Inspection Result	Original Circumference	Effective Circumference	Result Strength	Shell Decay Condition	Manufacture Year	Height	Class	Material	Species	Survey Date
6909	23	Fort Kent	47.24750160	-68.52800688	Reject	41.00	33.00	43.79	Decay Above and Below	1961	60	3	Wood	EC	10/6/19 8:59
6909	36	Fort Kent	47.24763900	-68.49986720	Reject	44.00	36.00	48.16	Good	1961	50	3	Wood	WRC	10/12/19 14:11
6909	36	Fort Kent	47.24766640	-68.49986740	Reject	46.00	38.00	50.22	Good	1961	50	3	Wood	WRC	10/12/19 14:13
6909	37	Fort Kent	47.24764150	-68.49724880	Reject	45.00	37.00	49.24	Good	1961	50	3	Wood	WRC	10/12/19 13:24
6909	37	Fort Kent	47.24766890	-68.49724910	Reject	46.00	38.00	50.22	Good	1961	50	3	Wood	WRC	10/12/19 13:25
6909	38	Fort Kent	47.24759943	-68.49454057	Reject	48.00	39.00	46.50	Good	1961	50	3	Wood	WRC	10/12/19 11:54
6909	38	Fort Kent	47.24761262	-68.49452969	Reject	45.00	37.00	49.24	Good	1961	50	3	Wood	WRC	10/12/19 11:57
6909	40	Fort Kent	47.24767014	-68.48922541	Reject	46.00	37.00	43.56	Good	1961	50	3	Wood	WRC	10/12/19 11:33
6909	40	Fort Kent	47.24768528	-68.48923371	Reject	46.00	37.00	43.56	Good	1961	50	3	Wood	WRC	10/12/19 11:35
6909	43	Fort Kent	47.24767720	-68.48101249	Reject	42.00	32.00	35.44	Decay Above and Below	1961	75	3	Wood	SP	10/4/19 8:44
6909	44	Fort Kent	47.24674628	-68.47904180	Priority Reject	44.00	30.00	21.82	Decay Above and Below	1961	70	3	Wood	SP	10/4/19 7:58
6909	44	Fort Kent	47.24674215	-68.47903285	Reject	42.00	36.00	57.08	Decay Below	1961	70	2	Wood	SP	10/4/19 8:05
6909	48	Fort Kent	47.24683845	-68.46992030	Reject	50.00	42.00	53.47	Decay Below	1961	60	2	Wood	WRC	10/8/19 14:58
6909	48	Fort Kent	47.24683339	-68.46988138	Reject	45.00	38.00	54.44	Decay Below	1961	60	2	Wood	WRC	10/8/19 14:59
6909	51	Fort Kent	47.24719084	-68.46094037	Reject	47.00	40.00	55.84	Good	1961	55	2	Wood	WRC	10/4/19 13:50
6909	51	Fort Kent	47.24719691	-68.46092313	Reject	50.00	42.00	53.47	Good	1961	50	2	Wood	WRC	10/4/19 13:52
6909	52	Fort Kent	47.24749978	-68.45798810	Reject	54.00	45.00	51.96	Decay Above and Below	1961	65	2	Wood	WRC	10/8/19 14:10
6909	62	Frenchville	47.24776510	-68.43361367	Reject	44.00	35.00	39.66	Decay Above and Below	1961	50	2	Wood	WRC	10/9/19 9:06
6909	64	Frenchville	47.24887179	-68.42966723	Priority Reject	39.00	28.00	28.71	Decay Above	1975	55	3	Wood	SP	10/9/19 9:47
6909	68	Frenchville	47.25292354	-68.42196795	Reject	42.00	34.00	45.54	Decay Below	1961	55	2	Wood	WRC	10/10/19 13:06
6909	68	Frenchville	47.25290593	-68.42191799	Reject	50.00	42.00	53.47	Decay Below	1961	55	2	Wood	WRC	10/10/19 13:08
6909	115	Frenchville	47.30913964	-68.35633058	Priority Reject	51.00	38.00	33.12	Decay Above	1961	70	2	Wood	WRC	10/14/19 13:59
6909	115	Frenchville	47.30912540	-68.35613160	Reject	50.00	40.00	40.20	Decay Below	1961	70	3	Wood	WRC	11/8/19 12:39
6909	120	Frenchville	47.31809242	-68.35609031	Visual Reject	0.00	0.00	0.00	Decay Above	1961	60	3	Wood	WRC	10/14/19 14:22
6909	120	Frenchville	47.31816896	-68.35625571	Reject	50.00	40.00	40.20	Decay Below	1961	60	3	Wood	WRC	10/14/19 14:24
6909	121	Frenchville	47.32008627	-68.35620533	Reject	50.00	42.00	53.47	Good	1961	55	3	Wood	WRC	10/15/19 8:49
6909	121	Frenchville	47.32007892	-68.35625120	Reject	50.00	42.00	53.47	Good	2002	55	3	Wood	WRC	10/15/19 8:52
6909	123	Frenchville	47.32259281	-68.35626510	Reject	41.00	35.00	56.37	Decay Below	1961	60	3	Wood	WRC	9/30/19 14:55
6909	128	Madawaska	47.32802920	-68.34543470	Reject	48.00	35.00	16.28	Decay Below	1961	65	2	Wood	WRC	9/30/19 12:57
6909	145	Madawaska	47.33637861	-68.31794832	Reject	45.00	36.00	40.20	Good	1961	60	2	Wood	SP	10/18/19 14:02
6909	148	Madawaska	47.34014742	-68.31494033	Reject	50.00	38.00	35.19	Decay Above	1961	60	2	Wood	WRC	10/16/19 9:59

Line 6909 built in 1961, comprised of 160 wood pole structures.

13% rejected in 2019 due to insufficient shell thickness, this quantity will continue to climb as this line ages



# Line 6909 Condition Continued...



Rotting wood pole crossarms and pole tops



# Line 6909 Condition Continued...



# Enhanced Inspection Methods



**Visual inspections performed by drone technology are providing engineers with a new and different view of asset condition**



# Example of a Closeup Drone Inspection Photo





# Enhanced Inspection Methods continued...Wood Pole Strength Assessment using Resistograph



Using a long thin needle the electric power consumption of the resistograph drilling device is measured and recorded. The resistance data gathered provides a high linear correlation between the measured values and the density of the penetrated wood.




# Resistograph Plot - Wood Pole in good condition

## Measuring / object data

Measurement no.:	47	Speed	: 3000 r/min	Diameter:	13,25 in
ID number	: 20694	Needle state:	---	Level	:
Drilling depth	: 14,99 in	Tilt	: -30°	Direction:	
Date	: 01/15/2019	Offset	: 56 / 289	Species	:
Time	: 11:33:03	Avg. curve	: off / off	Location	:
Feed	: 10 in/min			Name	:

## WoodInspector

Program	: Pole - EMERA 1.00	Sum decay	: 0,0%   0,0%   0,0%
Pole type	:	Heart rot	: 0,0%   0,0%   0,0%
Measurement	: Below soil level	Shell rot	: No   No
Defect pattern	: No decay	Remaining wall	: 50,0%   50,0%   50,0%
Result (auto)	: PASS	Strength	: 100,0%   100,0%   100,0%



## Assessment

## Comment

20694M047 (PASS).rgp


# Rejected Wood Pole – Heart Rot

## Measuring / object data

Measurement no.:	13	Speed :	3000 r/min	Diameter:	16,25 in
ID number :	20781	Needle state:	---	Level :	
Drilling depth :	18,01 in	Tilt :	-1°	Direction:	
Date :	10/23/2018	Offset :	93 / 388	Species :	
Time :	09:24:24	Avg. curve :	off / off	Location :	
Feed :	40 in/min			Name :	

## WoodInspector

Program :	Pole - EMERA 1.00	Sum decay :	40,7%	35,6%	76,3%
Pole type :		Heart rot :	40,7%	35,6%	76,3%
Measurement :	Auto diameter	Shell rot :	No	No	
Defect pattern:	Heart rot	Remaining wall:	9,3%	14,4%	11,8%
Result (auto) :	REJECT	Strength :	56,1%	74,3%	65,2%



## Assessment

## Comment

20781M013 (REJECT).rgp


# Rejected Wood Pole – Heart Rot & Shell Rot

## Measuring / object data

Measurement no.:	46	Speed :	3000 r/min	Diameter:	14,00 in
ID number :	20705	Needle state:	---	Level :	
Drilling depth :	17,19 in	Tilt :	-30°	Direction:	
Date :	01/17/2019	Offset :	111 / 415	Species :	
Time :	10:57:14	Avg. curve :	off / off	Location:	
Feed :	40 in/min	Name :			

## WoodInspector

Program :	Pole - EMERA 1.00	Sum decay :	2,9%	0,0%	2,9%
Pole type :		Heart rot :	2,9%	0,0%	2,9%
Measurement :	Below soil level	Shell rot :	No	Yes	
Defect pattern:	Heart+shell rot	Remaining wall:	21,7%	---	
Result (auto) :	REJECT	Strength :	89,7%	---	



## Assessment


## Comment

20705M046 (REJECT).rgp


# 2021 Project Work Summary

- Line 1176 – Easton (Rebuild Structure 42 - Border)
- Line 6930 – Caribou (Dow Rd to Maysville - Rebuild approx. 3 miles)
- Line 1176 - Easton & Presque Isle (Rebuild Structure 41 to Str. 3 - Construction Start)


# 20-Year MPS Transmission Line Rebuild History



# MPD Roadside Transmission Line Pole Age - 2016




# MPD Roadside Transmission Line Pole Age – 2021






# MPD ROW Transmission Line Pole Age - 2016



# MPD ROW Transmission Line Pole Age - 2021

## 2021 MPD ROW Transmission Pole Age



# MPD Solar Generation Interconnections

- Dist. (State) projects:
  - 36 Level 4 – 114.5 MW's total
  - 3 Level 2 – 0.5 MW's total
- Transmission (FERC) projects:
  - 2 – 25 MW's total
- Projects/circuits are studied to ensure system protection and reliability for adjacent customers is maintained

# MPD Transmission Studies

- Two Transmission studies initiated
  - Interface study by NBP
    - How will these generators impact interface connections?
  - Versant is conducting a Transmission study of the MPD system at the direction of, and in concert with, NMISA
    - Will these projects and the grid “play well together”?
- Both will be conducted at high generation, low load conditions

# Path to 100% Renewable

- Solar generation (nameplate): 122 MW
- Peak Load: approximately 95 MW
- This represents a solar generation to peak load of 128%: compare to...
  - California: 61%
  - Hawaii: 86%
- Voltage controls and Reactive power support (options are DVARs and Storage) will be necessary at both the circuit and transmission levels

# Complexity Will Increase

- DER's add system complexity – forecasting generation
- Power Quality controls (inverter based generation)
- Outage restoration methods with DER's
- Grid controls on a partly cloudy day